

Building Services & Const.  
 5900 Delaware Ave  
 Hainesport, NJ 08036  
 Phone: (609) 845-0077  
 Fax: (609) 845-0427

Q-10-135

TO Reliance Contracting  
 P.O. Box 1372  
 Marlton, NJ 08053

10/27/2010	11/25/2010	457 Church-Patio Demo- Replace	1
------------	------------	--------------------------------	---

This Project is for the removal and replacement of multi pour multi depth concrete patio. There is no access to the area for the concrete truck and all material must be brought in by wheelbarrow or buggy. The run from truck to porch is in excess of 200 feet. The removal involves saw cutting and column support during the course of the project. Pricing is based on visible conditions only. The interior pad has failed and has dropped 2 "

	1	Remove existing concrete by hand and wheelbarrow to dumpster	1650.00	1,650.00*
	1	Saw cut areas for removal	375.00	375.00*
	1	Dumpster for concrete removal	250.00	250.00*
	1	Support Columns and roof	875.00	875.00*
	1	Install new base of crushed concrete- bring in by hand	675.00	675.00*
	1	Install concrete portion of grade beam-bring in material by hand	625.00	625.00*
	1	Remove and reinstall existing drain currently installed in slab	175.00	175.00*
	1	install custom patio with flagstone inserts	2250.00	2,250.00*

\* means item is non-taxable

**TOTAL AMOUNT 6,875.00**

A photograph showing a concrete front step of a flagstone patio. The step is heavily stained with dark, irregular patches of melted debris. The surrounding patio is made of flagstones and is covered with fallen brown leaves. A white door frame is visible at the top of the step.

**FP2060708 - MELTED DEBRIS ON FRONT STEP  
OF FLAGSTONE PATIO**



**ADDITIONAL APPLICATION RISKS SPAULDING THE CONCRETE.**



**ROUGHLY 200SF AFFECTED BUT AT THIS POINT WE HAVE NOT COMMITTED PENDING YOUR REVIEW.**

